




Take a DIPP™ sooner with a Drop-In Plunge Pool




Small Round

WIDTH 2.5m HEIGHT 1.43m WEIGHT 5.2t WATER HEIGHT 1.2m approx CAPACITY 5,200ltr




Medium Round

WIDTH 3.5m HEIGHT 1.43m WEIGHT 7.2t WATER HEIGHT 1.2m approx CAPACITY 10,200ltr



Large Round

WIDTH 3.5m HEIGHT 1.63m WEIGHT 9.0t WATER HEIGHT 1.4m approx CAPACITY 12,000ltr



X Large Round

WIDTH 3.5m HEIGHT 1.83m WEIGHT 9.2t WATER HEIGHT 1.6m approx CAPACITY 14,200ltr



Square

WIDTH 2.48m LENGTH 2.48m HEIGHT 1.63m WEIGHT 7.2t WATER HEIGHT 1.4m approx CAPACITY 7,000ltr



Rectangle

WIDTH 2.48m LENGTH 4.8m HEIGHT 1.63m WEIGHT 10.0t WATER HEIGHT 1.4m approx CAPACITY 13,700ltr



DIPP63

WIDTH 3m LENGTH 6m HEIGHT 1.6m WEIGHT 12.7t WATER HEIGHT 1.45m approx CAPACITY 24,000ltr

PLUNGE POOL INCLUSIONS

- Fully reinforced 40Mpa concrete pool shell
- Solid concrete seat and top step (DIPP63 has concrete seat)
- Fitting of 2 x jet eyeballs & skimmer box
- Waterproofing of shell with Mapelastic Smart
- Tiling of pool internally with ceramic mosaic tiles and granite/travertine/limestone coping tiles
- Multi-coloured LED Light and transformer
- Form 15 engineering certificate and drawings

INSTALLATION INCLUSIONS

- QBCC Insurance
- Council fees by private certifier
- Supply and install gravel screed base for pool
- Installation of pool to manufacturer's specifications
- Temporary pool fence 3 weeks hire
- Filtration: Maytronics cartridge filtration package
- Installation of pool equipment including all pipe and fittings
- Excavation
- Includes lift into place if access permits from delivery truck (except DIPP63 – crane is required)
- Full on site pool startup, chemical balance and handover

OPTIONAL EXTRAS

- ASK ABOUT PRICES
- ▲ Mineral salts
 - ▲ Inverter heat pumps
 - ▲ Additional seat
 - ▲ Upgrade packages on equipment
 - ▲ External tiling
 - ▲ External paint
 - ▲ Solar thermal blankets
 - ▲ Pool robot cleaners



Entity Queensland Plunge Pools ABN 41 636 618 230 QBCC licence number # 15263480

NOT INCLUDED

- Delivery
- All electrical work
- Permanent fence
- Removal of excavated material
- Crane (if required)
- Concrete anti-flotation collar

